HIGH STREET

WHITE STREET

BELLEVILLE STREET

PR. ADA CURB RAMP WITH DETECTABLE WARNING STANDARD 424001

PR. COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (TYP.)

PR. ADA CURB RAMP WITH DETECTABLE WARNING STANDARD 424001

PR. PAVED GUTTER

PR. PAVED GUTTER

POT Sta 0+00.00

0+00

144.00'

BEGIN IMPROVEMENT STA. 0+02.46

34.0'

PR. PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH STA. 0+83.00 TO STA. 3+39.00 (MAINLINE SIDEWALK BY OTHERS)

30.50'

6.00'

6.00'

21.75'

4.00'

28.0'

POT Sta 3+89.96

END IMPROVEMENT STA. 3+87.16

150.00'

1

2

3

PR. ADA CURB RAMP WITH DETECTABLE WARNING STANDARD 424021

PR. LEVEL LANDING

PR. RAMP

PR. SIDE CURB

PR. TRANSITION AREA

PR. STEPS

EX. SIDEWALK (TO REMAIN)

STA. 2+09.29

PR. PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH

PR. ADA CURB RAMP WITH DETECTABLE WARNING STANDARD 424001

N

0 20 40 60

SCALE IN FEET

MODEL: Default
FILE NAME: P:\170396\4 CADD - DWG\4.7 Trans\170396_PlanSheet.dgn

USER NAME = esmith	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 9/5/2018	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN SHEET
BELLEVILLE ST.

SCALE: 1" = 20' | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CONTRACT NO.		
	ILLINOIS	FED. AID PROJECT		